

General rough cost estimate Cross walk at Scott Way

Cost breakdown:

- 2 Sidewalk bulb-outs, approximately 6' wide and 13' long with approximately 8' transitions on both sides, plus curb drains, ADA ramps, truncated domes for ADA = \$15k to \$20k range
- 2 Pedestrian signs with flashing beacon on top at bulb-outs = \$2k to \$2.5 k range
- 2 new reflective advance pedestrian signs = \$0.5k range
- Pedestrian cross walk striping with reflective markers = \$1k range
- Potential light pole in west side = \$5k range
- Electrical service = \$3k range

TOTAL = Approx. \$30k range