

Myers & Sons Hi-Way Safety Inc.

13310 5th St. Chino, Ca. 91710
(909) 591-1781 Fax (909) 364-2371

520 W. Grand Ave. Escondido, Ca. 92025
(760) 745-2250 Fax (760) 745-2094

Contractors License#785683 A-General Engineering, C-31 Work Zone Traffic Control, C-32 Highway Improvements

Prepared	CITY OF COMMERCE		Today's Date	2/11/2019
Location	VARIOUS LOCATIONS		Bid Date	
	COMMERCE, CA.		Delivery Date	
Reference	SEUNG W. YANG		Job #	
Phone		Fax	P.O. #	

Quotation

ITEM	QTY	UNIT	DESCRIPTION	UNIT	TOTAL
1	4	EA	R5-2 (MOD) 30X30, .080, Hi-Int.		
2	16	EA	SS1 NO THRU TRAFFIC, 24SS1 No Thru Traffic, 24x30, .080,		
3	4	EA	SS2 No Commercial Vehicles 4pm to 7pm..... 36x36,.080		
4	1	EA	SS3 No Commercial Vehicles/ No Right Turn Symbol.... 36x36		
5	1	EA	SS4 No Commercial Vehicles/ No Left Turn Symbol.... 36x36, .080		
6	1	EA	R2-1, Speed Limit (30), HI, 24x30, .080, White, Screened		
7	5	EA	W10-1, Railroad Crossing Advance, HI, 30x30, .080 Alum, Black/Yello		
8	1	EA	W48(ca) 3 Tracks, Hi-Int., 24x36, .080, Blk./Ylw.		
9	1	EA	R32 1 Hour Parking 7am to 6pm, 12x18, .080, Grn./Wht.		
10	2	EA	SR56A, "Photo Enforced", HI, 36x54, .080, White/Black		
11	1	EA	W10-2R, Parallel Railroad Crossing, HI, 30x30, .080 Alum, Black/Yel		
12	1	EA	W10-2L, Parallel Railroad Crossing, HI, 30x30, .080 Alum, Black/Yell		
13	1	EA	R1-1, Stop (R1), HI, 30x30, .080, White, Screened		
14	245.5	SF	Graffiti Overlay, 1160, 3M, Open Square Foot		
15	27	EA	Post, Perforated, 2in Sq, 14 Gauge, 10ft		
16	27	EA	Post Anchor, Perforated, 2.25in Sq, 12 Gauge, 30in		
17	27	EA	Post Sleeve, Perforated, 2.5in Sq, 12 Gauge, 18in		
18	1	EA	FURNISH AND INSTALLATION OF SIGNS	\$ 9,342.12	\$ 9,342.12
			ADDITIONAL ITEMS		
19	1	EA	R26(MOD) 12" X 18" R26(MOD) 12" x 18" .080, Hi-Int., Wht./Red		
20	1	EA	R26(MOD) 12" X 18" R26(MOD) 12" x 18" .080, Hi-Int., Wht./Red		
21	1	EA	R26(MOD) 12" X 18" R26(MOD) 12" x 18" .080, Hi-Int., Wht./Red		
22	1	EA	R26(MOD) 12" X 18" R26(MOD) 12" x 18" .080, Hi-Int., Wht./Red		
23	1	EA	R26(MOD) 12" X 18" R26(MOD) 12" x 18" .080, Hi-Int., Wht./Red		
24	1	EA	R1-5 18" X 18" .080, Hi-Int., Wht./Red YIELD HERE TO PED.		
25	11.25	SF	Graffiti Overlay, 1160, 3M, Open Square Foot		
26	6	EA	Post, Perforated, 2in Sq, 14 Gauge, 10ft		
27	6	EA	Post Anchor, Perforated, 2.25in Sq, 12 Gauge, 30in		
28	6	EA	Post Sleeve, Perforated, 2.5in Sq, 12 Gauge, 18in		
29	1	EA	FURNISH AND INSTALLATION OF SIGNS & SIDEWALK STRIPING	\$ 6,402.38	\$ 6,402.38

QUOTATION ACCEPTED BY				SUBTOTAL	\$ 15,744.50
CERTIFIED PAYROLL REQUIRED				TAX	
				FREIGHT	
				LABOR	
				OTHER	
				TOTAL	\$ 15,744.50

1. ALL RENTAL ITEMS PROPERTY OF HI-WAY SAFETY RENTALS INC.
2. INSTALLATIONS EXCLUDE ANY CUTTING OR COREING OF ASPHALT OR CONCRETE
3. CUSTOMER RESPONSIBLE FOR LOSS OR DAMAGE OF EQUIPMENT WHILE ON RENT
4. 1 MOVE IN INCLUDED UNLESS OTHERWISE NOTED.
5. THIS QUOTE WILL BE HONORED FOR AT LEAST 30 DAYS

To accept this quote please sign above and indicate whether certified payroll will be required and fax to 909.364.2371

ATTACHMENT 1